

AFRL-SR-BL-TR-01-

## REPORT DOCUMENTATION PAGE

0156

Public reporting burden for this collection of information is estimated to average 1 hour per response, including the time for reviewing the data needed, and completing and reviewing the collection of information. Send comments regarding this burden estimate or any other aspect of this collection of information, including suggestions for reducing this burden, to Washington Headquarters Services, Directorate for Information Operations and Reports, 1215 Jefferson Davis Highway, Suite 1204, Arlington, VA 22202-4302, and to the Office of Management and Budget Paperwork Reduction Project (0704-0188), Washington DC 20503.

1. AGENCY USE ONLY (Leave Blank)	2. REPORT DATE 20 Feb. 2001	3. REPORT TYPE AND DATES COVERED Final, 01 June 1999 - 30 Nov. 2000	
4. TITLE AND SUBTITLE Completion of the 9.5-inch Mach-6 Ludwig Tube: Enabling Low-Cost Hypersonic Quiet-Flow Experiments		5. FUNDING NUMBERS F49620-99-1-0278	
6. AUTHOR(S) Steven P. Schneider			
7. PERFORMING ORGANIZATION NAME(S) AND ADDRESS(ES) Aerospace Sciences Laboratory Purdue University Airport, Hangar 3 West Lafayette, IN 47906-3371		8. PERFORMING ORGANIZATION REPORT NUMBER	
9. SPONSORING/MONITORING AGENCY NAME(S) AND ADDRESS(ES) Air Force Office of Scientific Research/NA 801 N. Randolph St., Room 732 Arlington, VA 22203-1977		10. SPONSORING/MONITORING AGENCY REPORT NUMBER	
11. SUPPLEMENTARY NOTES			
12a. DISTRIBUTION/AVAILABILITY STATEMENT Unclassified, approved for public release.		12b. DISTRIBUTION CODE AIR FORCE OFFICE OF SCIENTIFIC RESEARCH (AFOSR) NOTICE OF TRANSMITTAL DTIC. THIS TECHNICAL REPORT HAS BEEN REVIEWED AND IS APPROVED FOR PUBLIC RELEASE LAW AFR 190-12. DISTRIBUTION IS UNLIMITED.	
13. ABSTRACT (Maximum 200 words) This grant supported fabrication of the 9.5-inch Mach-6 quiet-flow Ludwig tube at Purdue University. Due to delays in fabrication, the facility is not yet complete. Fabrication continues under AFOSR Grant F49620-00-1-0016 and other funds. Fabrication status is reported in several open-literature publications, here cited. Most parts of the tunnel have been completed and tested. The critical quiet-flow nozzle is nearly complete, with the last parts scheduled for shipment during early March 2000.			
14. SUBJECT TERMS Hypersonic laminar-turbulent transition, boundary layers, low-disturbance wind tunnels		15. NUMBER OF PAGES 3	
		16. PRICE CODE	
17. SECURITY CLASSIFICATION OF REPORT UNCLASSIFIED	18. SECURITY CLASSIFICATION OF THIS PAGE UNCLASSIFIED	19. SECURITY CLASSIFICATION OF ABSTRACT UNCLASSIFIED	20. LIMITATION OF ABSTRACT UNLIMITED

NSN 7540-01-280-5500

Standard Form 298 (Rev. 2-89)  
Prescribed by ANSI Std. Z39-18  
298-102

20010320 057

Final Report for DURIP Grant F49620-99-1-0278,  
1 June 1999 to 30 Nov. 2000. Grant titled 'Completion  
of the 9.5-inch Mach-6 Ludwig Tube:  
Enabling Low-Cost Hypersonic Quiet-Flow  
Experiments'

Steven P. Schneider, Associate Professor  
School of Aeronautical and Astronautical Engineering  
Aerospace Sciences Lab  
Purdue University Airport  
West Lafayette, IN 47906-3371  
steves@ecn.purdue.edu, 765-494-3343

February 20, 2001

## 1 Summary

This grant supported fabrication of the 9.5-inch Mach-6 quiet-flow Ludwig tube at Purdue University. Due to delays in fabrication, the facility is not yet complete. Fabrication continues under AFOSR Grant F49620-00-1-0016 and other funds. Fabrication status is reported in several open-literature publications, here cited. Most parts of the tunnel have been completed and tested. The critical quiet-flow nozzle is nearly complete, with the last parts scheduled for shipment during early March 2001.

## 2 Introduction

This grant supported fabrication of the tunnel cited. The progress of the design, fabrication, and testing is reported in References [1], [2], [3], [4], [5], [6], [7], and [8]. Early results, following completion, are to be presented in Ref. [9]. Cost information was reported in Ref. [10]. The finite-element stress-analysis for the large plexiglas window is to be reported in Ref. [11]. Work continues under AFOSR Grant F49620-00-1-0016 and Sandia contract BG-7114. These two grants support labor for facility completion and testing, as well as research into transition on scramjet forebodies (AFOSR) and blunt round cones (Sandia). Completion is currently scheduled for March 2001.

### 3 Brief Summary of Fabrication Status

The most critical element of a hypersonic quiet tunnel is the nozzle. The purchase order for fabrication of the present nozzle was awarded in Jan. 1999, about 2 years ago. Completion was delayed due to difficulties in fabricating the mandrel for the electroformed throat. The throat must have very high accuracy, very low waviness, and the tunnel performance is limited by the largest microscopic flaw in the mirror-finished throat. If a surface finish flaw develops during fabrication, the part must be discarded, and the process must start over. Three mandrels were fabricated in order to get a good one. Fortunately, the results shown in Ref. [6] show that the electroformed throat generated using the third mandrel looks good.

The remainder of the nozzle must also meet tight specifications for accuracy, low waviness, and the size of small steps near the joints in the nozzle. Seven of the 8 nozzle sections have been completed; the third is to be completed by early March. While the entire nozzle has not met the 0.001 inch accuracy specification and the 0.001 inch/inch waviness specification, the largest flaws are so far within 0.0015-in. in accuracy and the waviness remains generally within 0.0015 inch/inch. The electroformed nickel apparently became slightly elliptical during formation, with stress-relieving causing the cross-sections to become asymmetrical by about 1000 ppm. This left a step or steep wave of about 0.002 inches at the end of the electroform. Although this is within the  $Re_k = 12$  roughness specification, it remains a waviness concern.

The rest of the tunnel pieces have been completed, installed, and tested, as described in the references cited.

### 4 Acknowledgements

Design and fabrication of a complex and specialized wind tunnel requires the conscientious and skilled assistance of many persons, too numerous to mention here. The work has benefited from continued advice from the NASA Langley quiet tunnel group, especially Dr. Steve Wilkinson. The AFOSR program manager is Dr. Steven Walker, whose interest and patience is appreciated. The program manager for the nozzle fabrication is Mr. Larry DeMeno, of Dynamic Engineering Inc.; his conscientious attention to the many critical fabrication details is also appreciated. Mr. Terry Kubly, recently of Monticello Exchanger, Indiana, cooperated in the design of the aerodynamic pressure-vessel elements of the tunnel; this involved many tradeoffs between aerodynamics, operability, manufacturability, and the ASME pressure-vessel code.

### References

- [1] Steven P. Schneider. Design of a Mach-6 quiet-flow wind-tunnel nozzle using the e\*\*N method for transition estimation. Paper 98-0547, AIAA, January 1998.

- [2] Steven P. Schneider. Design and fabrication of a 9-inch Mach-6 quiet-flow Ludwig tube. Paper 98-2511, AIAA, June 1998.
- [3] Steven P. Schneider. Development of a Mach-6 quiet-flow wind tunnel for transition research. In *Laminar-Turbulent Transition*, pages 427–432, Berlin, 2000. Springer-Verlag. Proceedings of the 1999 IUTAM Conference, Sedona.
- [4] Steven P. Schneider. Fabrication and testing of the Purdue Mach-6 quiet-flow Ludwig tube. Paper 2000-0295, AIAA, January 2000.
- [5] Steven P. Schneider. Initial shakedown of the Purdue Mach-6 quiet-flow Ludwig tube. Paper 2000-2592, AIAA, June 2000.
- [6] Steven P. Schneider, Shann Rufer, Laura Randall, and Craig Skoch. Shakedown of the Purdue Mach-6 quiet-flow Ludwig tube. Paper 2001-0457, AIAA, January 2001.
- [7] Shann J. Rufer. Development of burst-diaphragm and hot-wire apparatus for use in the Mach-6 Purdue quiet-flow Ludwig tube. Master's thesis, School of Aeronautics and Astronautics, Purdue University, December 2000.
- [8] Steven P. Schneider. Laminar-flow design for a Mach-6 quiet-flow wind tunnel nozzle. *Current Science*, 79(6):790–799, 25 September 2000.
- [9] Steven P. Schneider, Craig Skoch, and Shann Rufer. Mean flow and noise measurements in the Purdue Mach-6 quiet-flow Ludwig tube. Paper 2001-XXXX, AIAA, June 2001. Submitted to the June 2001 AIAA Fluid Dynamics Meeting.
- [10] Steven P. Schneider. Laminar-turbulent transition in hypersonic boundary layers: Development of a high-Reynolds number Mach-6 quiet-flow testing capability. Final Report AFRL-SR-BL-TR-00-0025, AFOSR, February 2000. Citation AD-B251202 in DTIC. Distribution restricted to U.S. government agencies, due to proprietary cost information.
- [11] S.W. Kwon and Steven P. Schneider. Stress analysis for the window of the Purdue Mach-6 quiet-flow Ludwig tube. Technical Report 2002-XXXX, AIAA, January 2002. To be submitted to the Jan. 2002 AIAA Aerospace Sciences Meeting.